



PLANNING BOARD

P.O. Box 1305
Littleton, Massachusetts 01460

September 21, 1998

Recommended Schedule of Inspections for Subdivision Roadways

1. After clearing, grubbing and stump removal.
2. After drainage system (pipe, manholes, catch basins and other drainage structures) is installed but before it is backfilled.
3. Excavation and rough grade at subgrade. Roadway must be staked with grade stakes every 25 foot station.
4. After surface gravel is in and compacted.
5. On-site as first course of bituminous concrete is installed.
6. On-site as top course of bituminous concrete is installed.
7. Other inspections from time to time as special situations develop or as deemed appropriate by the inspector and the Planning Board.
8. Final inspection before acceptance by the Town of Littleton at a Town Meeting and concurrently with the review of as-built plan submittal.

Water Department inspects the installation of the water system.

Electric Department inspects the installation of electric utility system.

The Planning Board Engineer must be notified a minimum of 72 hours in advance whenever an inspection is indicated.